BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64
No:EE/YNK-D/E-PMT/05/2014-15 Dated: 11-12-2014

APPROVED TENDER SCHEDULE –'B'

Item No: 01

Name of Work:-:Providing signage and Ornamental boards in ward No- 01 of yelahanka Sub division.

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri.H S PALAKSHAMURTHY	
				Rate	Rate in Words
1	Providing and fixing **ornamental name boards** of size 2.10 X 0.50Mtrs and column of size 0.15 x 0.15 Mtrs of height 1.23 Mtrs of each board made of C C 1:1, 5:3 with necessary centrering and form work smooth finishing with reinforcement etc including fabrication charges painting concreting and transportation charges from manufacturing yard to the site of work all lead and lift loadiing and undloading and labour charges etc. complete as per the direction of the engineer incharge of the work	**Each**	14.00	6000.00	Rupees six thousand only
2	Retro - Reflectorised Traffic Signs :- Providing and fixing of retro - reflectorised cautionary, mandatory and informatory sign as per IRC : 67 - 2001 made of high intensity grade micro prismatic HIP type IV sheeting, fixed over alumium sheeting, 2mm thick firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 45cms x 45cm x 60cm, 60 cm below ground level as per approved drawing. The item includes earthwork excavation, Cement Concrete M-15 grade, 2 coats of approved colour synthetic enamel painting to the steel surface, as per clauses, including curing, cost of all materials, labour, loading, unloading, lead, lift, transporting etc., complete.(P.No.65, I.No.8.04 of NH SR 2009-10) Supported on a class B GI pipe 80mm outer dia, 3.50mtr long 60cm x 60cm square	**Each**	77.00	4500.00	Rupees four thousand five hundred only
3	KSRRB 300-1, Earth work excavation by manual means in **Hard soil** involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications. MORTH chapter 3. No. No. 138 S Item No 19.2 SR 2014-15	**cum**	3.02	105.84	Rupees one hundred five and paise eighty four only
4	KSRB 100-1 Loading and unloading ofstone aggregates / sand/ kanker/ Moorum /soil KSRRB M100-1 Placing tipper at loading with front end loader dumpting turning for return trip excluding time for haulged and return trip complete as per specification item No 17.1 page 130 and KSRB M.100.4.1 costof haulage excluding loading and unloading MORTH to a distance of 4.00 K.M (Item No 17.4 Page 130 (SR 2014-15)	cum	3.02	79.10	Rupees seventy nine and paise ten only

1

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri.H S PALAKSHAMURTHY	
				Rate	Rate in Words
5	KSRB- 4-1.5 : **Providing and laying in position plain cement concrete of nominal mix 1:2:4 using 20mm and down size** graded granite metal, machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications, specification. No. KBS 4.1.4.2,. No. 12/ Item No. 4.6/ PWD SR 2014-15	cum	3.02	5327.64	Rupees five thousand three hundred twenty seven and paise sixty four only
6	KSRRB 800-1: **painting two coats after filling the surface** with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specification MORTH chapter 8, No. 176/ Item No. 24.1/ PWD SR 2014-15	sqm	46.20	56.16	Rupees fifty six and paise sixteen only
7	KSRRB M800-9: **Painting new Kannada letter and figures of any shade with synthetic enamel paint block or any other approved** colour to give an even shade complete as per specification, ("ii) Hindi (Matras commas and the like not to be measured and paid for half letter shall be counted as half) MORTH specification No. 803, No. 178/ Item No. 24.9/ PWD SR 2014-15	cm	10000.00	0.70	Rupees paise seventy only

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.